

MSRDesign

LANGLEY LIBRARY | Signage Package

Addendum #1 07/03/2024

SIGNAGE SPECIFICATION

- 1.1 SCOPE**
 - A. Work includes materials, fabrication, and installation. Furnish and install all items as specified herein, and as indicated on the drawings.
 - B. Coordinate work and site access with the General Contractor and the Architect.
- 1.2 RELATED DOCUMENTS**
 - A. Drawings and general provisions of the contract, including general and supplementary conditions, apply to this work.
- 1.3 QUALITY ASSURANCE**
 - A. The requested work shall comply with all Federal and State codes, laws, and regulations, and all municipal ordinances or regulations in effect at the time work is being performed.
 - B. Any alternates or changes to sign types, materials, and construction methods specified in this document must be approved by the Architect.
 - C. Installer Qualifications: Engage an experienced installer who is familiar with the specified product and the installation of the specified product.
 - D. The manufacturer, subsidiary, or licensed agent shall be approved to supply the products specified, and to honor any claims against the product presented in accordance with the warranty.
 - E. For items which, when installed become fixed, provide shop drawings and details of connections, anchors, and adhesives.
 - F. Contractor shall guarantee that all material and work specified and furnished are guaranteed for one (1) year after punch list sign off, to be free of defects and faulty workmanship, and that any defective material or work shall be promptly repaired or replaced without additional cost to the Owner. The one-year guarantee shall include guarantee that materials, finishes, adhesives, and fasteners of all items, supplied and installed, will not peel, fade, crack, or release during the guarantee period.
- 1.4 SUBMITTAL**
 - A. Shop Drawings shall be submitted, indicating elevations of all sign types, all dimensions, letter and numerical style and sizes, schedules for all sign types, materials, colors, finishes, and all fabrication and installation details verified. Architect's approval of shop drawings is required before any work commences. All work shall be executed in strict accordance with drawings.
 - B. Descriptive literature shall be submitted to indicate materials, finishes, installation instructions and details for all sign materials.

- 1.4 SUBMITTAL (CONTINUE)**
 - C. Submit one sample of each exposed finish (which will be used for actual production) to the Architect for verification and approval prior to fabrication. Submit full size mock-ups within thirty (30) business days of award of bid for all sign types specified. All mock-ups shall become the property of the Owner and will not be permitted to be installed on the job site. All samples are subject to review by the Architect and all approved samples shall become the standard of comparison for all installation work. The Architect will review all submittals and will reject any work not meeting quality standards.
 - D. Maintenance Data: Provide in form suitable for inclusion in Owner's maintenance manuals. Data shall include purchase source listing and similar information. Recommendations for proper maintenance materials and procedures shall also be included for each finish specified. Include precautions against materials and methods which may be detrimental to finishes and performance.
- 1.5 LABOR**
 - A. All work shall be fabricated square, plumb, straight, and true.
 - B. Cut-out letters, numbers, and images shall be cut in continuous, even lines as indicated on drawings.
 - C. Fabricator shall provide all supporting and anchoring means as required for proper installation.
 - D. Accessories, anchorage, mounting devices, and spacers shall be guaranteed to be non-staining to adjacent walls and sign finishes for a period of five years after acceptance.
 - E. Exposed joints shall be continuously welded, ground, and polished smooth and shall not be visible. Corners shall be snug, neat, and tight fitting in an even, smooth plane.
 - F. Fabricator is responsible for providing proper thickness of materials to eliminate deformations.
- 1.6 DELIVERY, STORAGE, AND HANDLING**
 - A. Contractor shall deliver at the job site and install in its designated location all items specified herein by the date designated in the Invitation to Bid.
 - B. Delivery shall be made to the job site during normal business hours: TBD. The Contractor shall provide adequate facilities and labor for unloading.
 - C. Inspect items upon delivery for damage. Minor damages may be repaired provided finished repairs are equal to the quality of new work and acceptable to the Owner and approved by the Architect.
 - D. Product shall be handled and stored to prevent damage.


- 1.7 PROJECT CONDITIONS**
 - A. Field Measurements: Verify all conditions, sizes, locations, and quantities before order and fabrication.
 - B. Field Verify all color of adjacent wall(s) before installation. Issue shop drawings indicating sign and wall color to be approved.
- 1.8 SEQUENCING AND SCHEDULING**
 - A. Sequence delivery of signs to minimize possibility of damage during the remainder of the construction period.
- 1.9 ENGINEERING**
 - A. All structural engineering is the responsibility of the successful bidder. All specifications pertaining to materials and fabrications are to establish minimum material and physical appearance only.
- 2.0 MATERIALS**
 - A. All materials used in production and installation shall be new, of top quality and free of defects.
 - B. Sheet plastic shall be free of wrinkles or imperfections from fabrication. All surfaces shall be free of scratches and shall be clean and polished at completion of installation.
 - C. Colors shall meet specifications on drawings. Sample colors shall be submitted for Architect's approval.
 - D. All inks, paints, and stains are to be applied evenly, without scratches, peeling, uneven edges, marks, etc. Workmanship in conjunction with finish and formation of letters must be recommended by the manufacturer for inks and paints, shall be included in the work as part of the finishes surface work at no extra cost to the Owner.
 - E. All mounting hardware, although not expressly stated in the specification, shall be included with the bid price. Furnish all mounting and anchoring hardware and devices as required to completely install all work. All fastening devices must meet fabricator recommendations. Bidders are required to visit the site prior to bidding for field understanding of mounting surfaces.
 - F. Font: See drawing of details for fonts. Signage contractor to be responsible for requirements of upper and lower case of copy as required by ADA. Alternate letter forms must be approved by Architect. Font color to match color specified by Architect except as otherwise noted herein. All letter forms must be so aligned as to maintain a base line parallel to the sign format. Margins must be maintained consistent within the sign types.

- 2.0 MATERIALS (CONTINUE)**
 - G. Letter size: All letter forms and work spacing shall be produced by photo mechanical methods and shall be set 'normal' except as directed by the Architect.
 - H. Grade 2 Braille: Braille to be raised 1/32" minimum from plaque first surface by Raster Method processes. Braille to comply with relevant ADA regulations and the requirements indicated for size, style, spacing, content, and positions Translation of sign copy is the responsibility of the fabricator.
- 3.0 EXECUTION**
- 3.1 EXAMINATION**
 - A. Contractor shall be responsible for inspection of project site and approval of installation conditions for this work. Proceed with installation only after unsatisfactory conditions have been corrected.
- 3.2 FABRICATION**
 - A. All signs and related work, including all structural supports and connections, shall be fabricated in a manner to withstand weight load, double of actual item installed.
 - B. All fabrication shall be in accordance with the highest standards of the trade. All signs and components shall be complete and free from visual and structural flaws.
 - C. All work shall be carefully fitted with minimum size joints, accurately located, and rigidly assembled. All corners, joints, miters, etc. shall be accurately machined, filed, and fitted. All joints shall be hairline unless otherwise indicated.
 - D. All paints shall be applied in strict conformance to manufacturer recommendations. All paint shall be carefully applied to avoid sags, runs, orange peel, or other unacceptable finish surface conditions. All material to which paint is to be applied shall be properly degreased, cleaned, and treated if required for the best possible results.
- 3.3 INSTALLATION**
 - A. Sign contractor to examine the substrates and conditions under which the installation is to be performed and notify the Architect of conditions detrimental to the proper and timely completion of the work. Do not proceed with the installation until unsatisfactory conditions have been corrected.

- 3.3 INSTALLATION (CONTINUE)**
 - B. Install items at locations shown on drawings. Communicate any discrepancies observed in the field to Architect prior to installation.
 - C. Install all items as shown on drawings, with all dust and dirt removed. Tape and tape marks are to be removed from surfaces. Contractor shall remove all crating, plastic coverings, and debris from the project, leaving premises in showroom condition; free from dust and ready for the Owner's use, unless otherwise instructed by Architect. Replace all damaged units as directed by the Architect.
 - D. Precaution shall be taken to protect building from damage. Any damage to walls, floors, or carpet noticed at the time of installation shall be brought to the attention of the Owner.
 - E. Coordinate all work with other contractors working on project and with any future contracts. Work schedule and rules for contractor will be enforced. The work schedule will be established upon approval by administration.
 - F. The interior signage contractor shall obtain and pay for all required permits from authorities having jurisdiction.
- 3.4 ADJUSTMENT AND CLEANING**
 - A. Immediately upon completion of installation, clean components and surfaces. Remove surplus materials, rubbish, and debris resulting from installation upon completion of work or leave areas of installation in neat, clean condition.
- 3.5 PROTECTION**
 - A. All surfaces and sign components shall be protected until final installation and approval by Owner or Architect (punch list). Any work damaged or discolored in any way before installation and approval occurs shall be corrected by the fabricator without additional cost to the Owner.
 - B. Advise Owner of additional protection needed to ensure that items will be without damage or deterioration until completion of construction.
- 3.6 SIGN REPLACEMENT MANUAL**
 - A. Contractor shall provide the Owner with a sign replacement manual after completion of all signage installation. Manual shall contain all information required to order all sign types. Each sign type should be described in such a format the Owner only need fill out the requirements for copy, after selecting sign type.
 - B. The following information should be included for each type:
 - 1. Unit Price and
 - 2. Diagram showing copy location, dimensions, color placement, copy sizes, and installation info.

SHT NO	SHEET NAME
A751	SPECIFICATIONS, SIGN SCHEDULE, AND SHEET INDEX
A753	AREA IDENTIFICATION SIGNAGE
A754	DIRECTIONAL SIGNAGE
A755	INFORMATIONAL SIGNAGE
A761	LOWER LEVEL SIGNAGE PLAN
A762	MAIN LEVEL SIGNAGE PLAN
A763	SIGNAGE ELEVATIONS

TEXT MOUNTING HEIGHT



MINIMUM HEIGHT: BASELINE OF LOWEST COPY MOUNTED NO LOWER THAN 48" ABOVE FLOOR
MAXIMUM HEIGHT: BASELINE OF HIGHEST COPY MOUNTED NO HIGHER THAN 60" ABOVE FLOOR

MATERIAL/PRODUCT ID - SIGNAGE

- FILM-1** GLASS FILM
MFR: SKYLINE DESIGN;
PRODUCT: FILM STUDIO;
ROLL SIZE: 59" W x 45' L;
CONTENT: PVC-FREE POLYESTER FILM;
PRIVACY: SOLID ETCH;
PATTERN: GRADIENT, BOTTOM TO TOP (INVERTED);
BACKING: WATER-BASED PRESSURE-SENSITIVE ADHESIVE;
SIZE: SEE ELEVATION;
ACCEPTABLE ALTERNATE: 3M DUSTED CRYSTAL;
- FILM-2** DECAL
MATERIAL: NON-PVC FILM;
COLOR: CMYK: 65, 61, 60, 46 (CHARCOAL) TYPICAL. CMYK: 0, 0, 0, 0 (WHITE) WHERE NOTED ON SCHEDULE;
- PT-1B** LIGHT BLUE PAINT
MFR: SHERWIN WILLIAMS;
COLOR: SW 9054 LITTLE BOY BLU;
- PT-1D** DARK BLUE PAINT (TO MATCH PLAM-2B)
MFR: SHERWIN WILLIAMS;
COLOR: SW6243 DISTANCE;

SIGNAGE LEGEND



SIGNAGE TYPE KEY

- NOT ALL TYPES MAY BE USED
- XS** EXISTING
 - REGULATORY**
 - RP** EVACUATION PLAN
 - RO** MAXIMUM OCCUPANCY
 - RS** STAIRWELL POSTING
 - RE** EXIT STAIR
 - AREA IDENTIFICATION**
 - AD** BUILDING ID - DIMENSIONAL
 - AF** BUILDING ID - FILM/DECAL
 - AM** BUILDING ID - MONUMENT
 - AR** ROOM ID
 - AP** ROOM ID - PICTOGRAM
 - AI** ROOM ID - CHANGEABLE INSERT
 - DIRECTIONAL**
 - DB** BLADE SIGN
 - DF** FILM/DECAL
 - DD** DIMENSIONAL
 - DP** PLAQUE
 - DC** CEILING HUNG
 - DM** MONUMENT / FREE STANDING
 - DIR** FLOOR PLAN DIRECTORY
 - INFORMATIONAL**
 - IH** HOURS OF OPERATION
 - IR** BUILDING REGULATIONS
 - IO** OPEN / CLOSED
 - IF** FILM/DECAL
 - ID** DIMENSIONAL
 - IP** PLAQUE
 - IC** CEILING HUNG
 - IE** END PANEL
 - II** CHANGEABLE INSERT
 - IS** SHELF TOPPER
 - CUSTOM GRAPHIC/DONOR**
 - GF** FILM/DECAL
 - GD** DIMENSIONAL
 - GW** WALL COVERING
 - GP** PLAQUE

PICTOGRAMS TYPES

AREA IDENTIFICATION			
TYPE	PICTOGRAM	MESSAGE	COMMENT
LOWER LEVEL			
AR-005	10	STUDY ROOM	SEE GENERAL NOTES FOR GLASS MOUNTING
AR-006	-	IT ROOM	
AP-002	1, 2, 3	RESTROOM	CENTER ON DOOR
AR-001	-	PUMP ROOM	CENTER ON DOOR
MAIN LEVEL			
AP-113	1, 2, 3	RESTROOM	
AP-113	1, 2, 3	RESTROOM	
AP-106	10	STUDY ROOM	DARK BLUE SIGN WITH WHITE ROWMARK
AR-105	-	MANAGERS OFFICE	DARK BLUE SIGN WITH WHITE ROWMARK
AR-103	-	FOCUS ROOM	
AR-108	-	MEETING ROOM	DARK BLUE SIGN WITH WHITE ROWMARK
AR-111	-	STORAGE	
AR-111	-	STORAGE	

DIRECTIONAL				
TYPE	QTY	PICTOGRAM	MESSAGE	COMMENTS
LOWER LEVEL				
DB	1	13	SELF CHECKOUT	
DP	1	9, 10, 12, 17, 18	-	FOR MESSAGE, SEE VECTOR FILE PROVIDED

CUSTOM GRAPHIC				
TYPE	QTY	MESSAGE	COMMENT	
LOWER LEVEL				
GF-1	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
MAIN LEVEL				
GF-2	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-3	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-4	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-5	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-6	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	

INFORMATIONAL					
TYPE	PICTOGRAM	QTY	MESSAGE	COMMENTS	
LOWER LEVEL					
IF-1	6, 7	1	-		
IF-6	-	1	WHEELCHAIR LIFT		
IF-7	-	1	STAFF ONLY	CENTER ON DOOR, 60" AFF	
IS	-	25	-	CONFIRM MESSAGE WITH OWNER	
MAIN LEVEL					
ID-1	14	1	RETURNS		
IF-2	-	1	HOLDS		
IF-3	15	1	BUSINESS CENTER		
IF-4	16	1	PUBLIC COMPUTERS		
IF-5	4	1	INFORMATION		
IF-6	-	1	WHEELCHAIR LIFT		
IF-7	-	1	STAFF ONLY	CENTER ON DOOR, 60" AFF	
IF-8	-	1	PICK UP	DECAL COLOR: WHITE	
IF-9	14	1	RETURNS		
IH	11	1	-	FOR TYPE SETTING, SEE AI FILE PROVIDED	
IS	-	7	-	CONFIRM MESSAGE WITH OWNER	

AREA IDENTIFICATION | AP & AR

CHARACTERS
 Font Myriad Pro
 Style Light (Bold Room Numbers)
 Tracking 20
 Case Upper Case
 Align Left, see dimensions and details
 Size 5/8" high U.N.O. (based on upper case "T")

MATERIALS
 Acrylic Clear matte acrylic, 1/4" thick
 Rowmark CMYK: 65, 61, 60, 46 (**CHARCOAL**)
 Paint CMYK: 0, 0, 0, 0 (**WHITE**)

On dark blue field:
 Acrylic Clear matte acrylic, 1/4" thick
 Rowmark CMYK: 0, 0, 0, 0 (**WHITE**)
 Paint Match **P1-D (DARK BLUE)**

*See schedule for locations of **DARK BLUE** signage

FABRICATION
 Back-paint acrylic panel **WHITE/DARK BLUE**. Cut characters from Rowmark matching **CHARCOAL/WHITE**, and adhere to front of acrylic panel.

BRAILLE
 Raised Grade 2 Braille, clear. To adhere to the Americans with Disabilities Act Accessibility Guidelines (ADAAG).

MOUNTING
 Flush mount using VHB tape, per installation instructions in the sign specifications section and the locations detailed in the sign locations section.



When mounted on glass contractor to provide color matching acrylic back panel to hide tape.

Glass-mounted signs identified in schedules with asterisks () see schedules sheets and floor plans.

PICTOGRAM (when applicable)
 Architect will provide all symbols and pictograms as vectored image files.



Use Rowmark matching **CHARCOAL/WHITE**

AP PICTOGRAM



* USE ON DARK BLUE FIELD

AR ROOM



* USE ON DARK BLUE FIELD

GENERAL NOTES

- ROOM NAMES AND DOOR NUMBERS ARE SUBJECT TO CHANGE. VERIFY ALL SIGN MESSAGE CONTENT WITH ARCHITECT PRIOR TO FABRICATION
- CENTER ALL PICTOGRAMS, MESSAGES, AND CONTENT ON SIGNS U.N.O.
- SEE SIGN SCHEDULE FOR QUANTITIES, MESSAGE, AND PICTOGRAM USED
- HATCHED AREA REPRESENTS PLACEMENT OF PICTOGRAM, MAXIMUM OF FOUR PICTOGRAMS PER SIGNAGE TYPE
- SEE SCHEDULE FOR LOCATION OF DARK BLUE SIGNS
- SIGN MOUNTING HEIGHTS REFERENCED START AT FINISH FLOOR.
- ALL SIGNS SHALL BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE BUILDING CODES AND THE AMERICAN WITH DISABILITIES ACT (ADA) ACCESSIBILITY GUIDELINES
- ALL TYPEFACE HEIGHT MEASUREMENTS BASED ON CAPITAL "T"
- WHEN MOUNTED ON GLASS AND NOT ACCOMPANIED BY A ROOM SIGN, CONTRACTOR TO PROVIDE BACK PANEL OR ACCOMPANYING ROOM SIGN ON OPPOSITE SIDE OF GLASS TO HIDE TAPE MOUNTING
- SIGNS TO BE MOUNTED ON FINISH WALLS OTHER THAN PAINTED GYPSUM WALLS TO BE NOTED IN SHOP DRAWINGS, AND PROPER INSTALLATION AND MOUNTING METHODS SHALL BE APPROVED BEFORE FABRICATION
- SEE PLANS AND ELEVATIONS FOR PLACEMENT DETAILS
- ARCHITECT TO PROVIDE VECTOR FILE FOR TYPE SETTING INFORMATION
- CONTACT ARCHITECT FOR FONT FILE(S), DOWNLOADS, OR QUESTIONS RELATED TO TYPE SETTING
- FIELD VERIFY ALL CONDITIONS

PICTOGRAMS TYPES



MINIMUM HEIGHT: BASELINE OF LOWEST COPY MOUNTED NO LOWER THAN 48" ABOVE FLOOR
MAXIMUM HEIGHT: BASELINE OF HIGHEST COPY MOUNTED NO HIGHER THAN 60" ABOVE FLOOR

Drawing 2024 Copyright © MSR Design & Fabrication, Ltd. 7/20/24 9:11:13 AM C:\p\proj\2024\18_LAN_1852_Cover_Signage_Pictograms.dwg


DIRECTIONAL | DP

CHARACTERS
 Font Myriad Pro
 Style Regular
 Tracking 20
 Case Title Case
 Align Left, see dimensions and details
 Color CMYK 65, 61, 60, 46 (**CHARCOAL**)
 Size 1 1/2" high (based on upper case "N")

MATERIALS
 FILM-2, color to match **CHARCOAL**.

DP FLOOR PLAN DIRECTORY

- SEE PLANS AND ELEVATIONS FOR PLACEMENT DETAILS
- SEE A1 FILE PROVIDED FOR TYPE SETTING INFORMATION




DIRECTIONAL | DB

CHARACTERS
 Font Myriad Pro
 Style Regular
 Case Title Case
 Align Varies, see dimensions and details
 Size 1 1/2" high (based on upper case "N")

MATERIALS
 Acrylic Matte standard white, 1/2" thick
 Aluminum Anodized, 1/4" thick
 Characters Cut characters (Rowmark) to match CMYK: 65, 61, 60, 46 (**CHARCOAL**)

FABRICATION
 Darkened anodized aluminum (**CHARCOAL**) mounting plate, with counter sunk fasteners. Cut characters (Rowmark) adhered to both sides of sign as shown.


DB BLADE SIGN



GENERAL NOTES

- ROOM NAMES AND DOOR NUMBERS ARE SUBJECT TO CHANGE. VERIFY ALL SIGN MESSAGE CONTENT WITH ARCHITECT PRIOR TO FABRICATION
- CENTER ALL PICTOGRAMS, MESSAGES, AND CONTENT ON SIGNS U N O.
- SEE SIGN SCHEDULE FOR QUANTITIES, MESSAGE, AND PICTOGRAM USED
- HATCHED AREA REPRESENTS PLACEMENT OF PICTOGRAM, MAXIMUM OF FOUR PICTOGRAMS PER SIGNAGE TYPE
- SEE SCHEDULE FOR LOCATION OF DARK BLUE SIGNS
- SIGN MOUNTING HEIGHTS REFERENCED START AT FINISH FLOOR.
- ALL SIGNS SHALL BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE BUILDING CODES AND THE AMERICAN WITH DISABILITIES ACT (ADA) ACCESSIBILITY GUIDELINES
- ALL TYPEFACE HEIGHT MEASUREMENTS BASED ON CAPITAL "T"
- WHEN MOUNTED ON GLASS AND NOT ACCOMPANIED BY A ROOM SIGN, CONTRACTOR TO PROVIDE BACK PANEL OR ACCOMPANYING ROOM SIGN ON OPPOSITE SIDE OF GLASS TO HIDE TAPE MOUNTING
- SIGNS TO BE MOUNTED ON FINISH WALLS OTHER THAN PAINTED GYPSUM WALLS TO BE NOTED IN SHOP DRAWINGS, AND PROPER INSTALLATION AND MOUNTING METHODS SHALL BE APPROVED BEFORE FABRICATION
- SEE PLANS AND ELEVATIONS FOR PLACEMENT DETAILS
- ARCHITECT TO PROVIDE VECTOR FILE FOR TYPE SETTING INFORMATION
- CONTACT ARCHITECT FOR FONT FILE(S), DOWNLOADS, OR QUESTIONS RELATED TO TYPE SETTING
- FIELD VERIFY ALL CONDITIONS

PICTOGRAMS TYPES



INFORMATIONAL | iD


CHARACTERS
 Font Myriad Pro
 Style Regular
 Tracking 20
 Case Title Case
 Align Left, see dimensions and details
 Size 4" high (based on upper case "N")

MATERIALS
 Aluminum Anodized, 3/8" thick
 Color Match: CMYK: 65, 61, 60, 46 (**CHARCOAL**)

FABRICATION
 CNC cut aluminum characters.

MOUNTING
 Pin mounted lettering, held off surface below by 1/4" min.

iD DIMENSIONAL




INFORMATIONAL | iF

CHARACTERS
 Font Myriad Pro
 Style Regular
 Tracking 20
 Case Title Case
 Align Left, see dimensions and details
 Color CMYK: 65, 61, 60, 46 (**CHARCOAL**), typical.
 CMYK: 0, 0, 0, 0 (**WHITE**) where noted on schedule
 Size 1 1/2" high (based on upper case "N")

MATERIALS
FILM-2, color to match **CHARCOAL**, typical.
FILM-2, color to match **WHITE** where noted on schedule.

iF FILM/DECAL




INFORMATIONAL | iS

CHARACTERS
 Font Myriad Pro
 Style Regular
 Case Title Case
 Align Centered, see dimensions and details
 Size 1 1/2" high (based on upper case "N")

MATERIALS
 Acrylic Matte standard white, 1/4" thick
 Text Cut characters (Rowmark) to match CMYK: 65, 61, 60, 46 (**CHARCOAL**)

FABRICATION
 Weighted base painted to match **PT-1B**. Cut characters (Rowmark) adhered to front face of sign as shown. Provide 1/16" cork foot layer, cover entire bottom of sign base.

iS SHELF TOPPER - WEIGHTED BASE




INFORMATIONAL | iH

CHARACTERS
 Font Myriad Pro
 Style Regular
 Case Upper Case
 Align Varies, see Ai provided by Architect
 Color CMYK: 0, 0, 0, 0 (**WHITE**)
 Size Varies, see Ai provided by Architect (based on upper case "N")

MATERIALS
FILM-2, color to match **WHITE**.

iH HOURS OF OPERATION


- SEE PLANS AND ELEVATIONS FOR PLACEMENT DETAILS
- CONFIRM HOURS OF OPERATION WITH OWNER
- SEE AI FILE PROVIDED BY ARCHITECT FOR TYPESETTING INFORMATION



GENERAL NOTES

- ROOM NAMES AND DOOR NUMBERS ARE SUBJECT TO CHANGE. VERIFY ALL SIGN MESSAGE CONTENT WITH ARCHITECT PRIOR TO FABRICATION
- CENTER ALL PICTOGRAMS, MESSAGES, AND CONTENT ON SIGNS UNLESS NOTED
- SEE SIGN SCHEDULE FOR QUANTITIES, MESSAGE, AND PICTOGRAM USED
- HATCHED AREA REPRESENTS PLACEMENT OF PICTOGRAM, MAXIMUM OF FOUR PICTOGRAMS PER SIGNAGE TYPE
- SEE SCHEDULE FOR LOCATION OF DARK BLUE SIGNS
- SIGN MOUNTING HEIGHTS REFERENCED START AT FINISH FLOOR.
- ALL SIGNS SHALL BE INSTALLED IN ACCORDANCE WITH ALL APPLICABLE BUILDING CODES AND THE AMERICAN WITH DISABILITIES ACT (ADA) ACCESSIBILITY GUIDELINES
- ALL TYPEFACE HEIGHT MEASUREMENTS BASED ON CAPITAL "I"
- WHEN MOUNTED ON GLASS AND NOT ACCOMPANIED BY A ROOM SIGN, CONTRACTOR TO PROVIDE BACK PANEL OR ACCOMPANYING ROOM SIGN ON OPPOSITE SIDE OF GLASS TO HIDE TAPE MOUNTING
- SIGNS TO BE MOUNTED ON FINISH WALLS OTHER THAN PAINTED GYPSUM WALLS TO BE NOTED IN SHOP DRAWINGS, AND PROPER INSTALLATION AND MOUNTING METHODS SHALL BE APPROVED BEFORE FABRICATION
- SEE PLANS AND ELEVATIONS FOR PLACEMENT DETAILS
- ARCHITECT TO PROVIDE VECTOR FILE FOR TYPE SETTING INFORMATION
- CONTACT ARCHITECT FOR FONT FILE(S), DOWNLOADS, OR QUESTIONS RELATED TO TYPE SETTING
- FIELD VERIFY ALL CONDITIONS

PICTOGRAMS TYPES



SIGNAGE LEGEND

XXX-###
SIGN TYPE LOCATION OR ROOM NUMBER*
(*FOR ROOM IDENTIFICATION TYPES ONLY)


SIGNAGE TYPE KEY

NOT ALL TYPES MAY BE USED

- XS EXISTING
- REGULATORY**
- RP EVACUATION PLAN
- RO MAXIMUM OCCUPANCY
- RS STAIRWELL POSTING
- RE EXIT STAIR
- AREA IDENTIFICATION**
- AD BUILDING ID - DIMENSIONAL
- AF BUILDING ID - FILM/DECAL
- AM BUILDING ID - MONUMENT
- AR ROOM ID
- AP ROOM ID - PICTOGRAM
- AI ROOM ID - CHANGEABLE INSERT
- DIRECTIONAL**
- DB BLADE SIGN
- DF FILM/DECAL
- DD DIMENSIONAL
- DP PLAQUE
- DC CEILING HUNG
- DM MONUMENT / FREE STANDING
- DIR FLOOR PLAN DIRECTORY
- INFORMATIONAL**
- IH HOURS OF OPERATION
- IR BUILDING REGULATIONS
- IO OPEN / CLOSED
- IF FILM/DECAL
- ID DIMENSIONAL
- IP PLAQUE
- IC CEILING HUNG
- IE END PANEL
- II CHANGEABLE INSERT
- IS SHELF TOPPER
- CUSTOM GRAPHIC/DONOR**
- GF FILM/DECAL
- GD DIMENSIONAL
- GW WALL COVERING
- GP PLAQUE

PICTOGRAMS TYPES

AREA IDENTIFICATION				
TYPE	PICTOGRAM	MESSAGE	COMMENT	
LOWER LEVEL				
AR-005	10	STUDY ROOM	SEE GENERAL NOTES FOR GLASS MOUNTING	
AR-006	-	IT ROOM		
AP-002	1, 2, 3	RESTROOM	CENTER ON DOOR	
AR-001	-	PUMP ROOM	CENTER ON DOOR	
MAIN LEVEL				
AP-113	1, 2, 3	RESTROOM		
AP-113	1, 2, 3	RESTROOM		
AP-106	10	STUDY ROOM	DARK BLUE SIGN WITH WHITE ROWMARK	
AR-105	-	MANAGERS OFFICE	DARK BLUE SIGN WITH WHITE ROWMARK	
AR-103	-	FOCUS ROOM		
AR-108	-	MEETING ROOM	DARK BLUE SIGN WITH WHITE ROWMARK	
AR-111	-	STORAGE		
AR-111	-	STORAGE		
DIRECTIONAL				
TYPE	QTY	PICTOGRAM	MESSAGE	COMMENTS
MAIN LEVEL				
DB	1	13	SELF CHECKOUT	
DP	19, 10, 12, 17, 18	-	-	FOR MESSAGE, SEE VECTOR FILE PROVIDED
INFORMATIONAL				
TYPE	PICTOGRAM	QTY	MESSAGE	COMMENTS
LOWER LEVEL				
IF-1	6, 7	1	-	
IF-6	-	1	WHEELCHAIR LIFT	
IF-7	-	1	STAFF ONLY	CENTER ON DOOR, 60" AFF
IS	-	25	-	CONFIRM MESSAGE WITH OWNER
MAIN LEVEL				
ID-1	14	1	RETURNS	
IF-2	-	1	HOLDS	
IF-3	15	1	BUSINESS CENTER	
IF-4	16	1	PUBLIC COMPUTERS	
IF-5	4	1	INFORMATION	
IF-6	-	1	WHEELCHAIR LIFT	
IF-7	-	1	STAFF ONLY	CENTER ON DOOR, 60" AFF
IF-8	-	1	PICK UP	DECAL COLOR: WHITE
IF-9	14	1	RETURNS	
IH	11	1	-	FOR TYPE SETTING, SEE AI FILE PROVIDED
IS	-	7	-	CONFIRM MESSAGE WITH OWNER
CUSTOM GRAPHIC				
TYPE	QTY	MESSAGE	COMMENT	
LOWER LEVEL				
GF-1	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
MAIN LEVEL				
GF-2	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-3	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-4	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-5	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-6	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	



SIGNAGE LEGEND

XXX-###
SIGN TYPE LOCATION OR ROOM NUMBER
(FOR ROOM IDENTIFICATION TYPES ONLY)

SIGNAGE TYPE KEY

NOT ALL TYPES MAY BE USED


- XS EXISTING
- REGULATORY**
- RP EVACUATION PLAN
- RO MAXIMUM OCCUPANCY
- RS STAIRWELL POSTING
- RE EXIT STAIR
- AREA IDENTIFICATION**
- AD BUILDING ID - DIMENSIONAL
- AF BUILDING ID - FILM/DECAL
- AM BUILDING ID - MONUMENT
- AR ROOM ID
- AP ROOM ID - PICTOGRAM
- AI ROOM ID - CHANGEABLE INSERT
- DIRECTIONAL**
- DB BLADE SIGN
- DF FILM/DECAL
- DD DIMENSIONAL
- DP PLAQUE
- DC CEILING HUNG
- DM MONUMENT / FREE STANDING
- DIR FLOOR PLAN DIRECTORY
- INFORMATIONAL**
- IH HOURS OF OPERATION
- IR BUILDING REGULATIONS
- IO OPEN / CLOSED
- IF FILM/DECAL
- ID DIMENSIONAL
- IP PLAQUE
- IC CEILING HUNG
- IE END PANEL
- II CHANGEABLE INSERT
- IS SHELF TOPPER
- CUSTOM GRAPHIC/DONOR**
- GF FILM/DECAL
- GD DIMENSIONAL
- GW WALL COVERING
- GP PLAQUE

PICTOGRAMS TYPES


AREA IDENTIFICATION				
TYPE	PICTOGRAM	MESSAGE	COMMENT	
LOWER LEVEL				
AR-005	10	STUDY ROOM	SEE GENERAL NOTES FOR GLASS MOUNTING	
AR-006	-	IT ROOM		
AP-002	1, 2, 3	RESTROOM	CENTER ON DOOR	
AR-001	-	PUMP ROOM	CENTER ON DOOR	
MAIN LEVEL				
AP-113	1, 2, 3	RESTROOM		
AP-113	1, 2, 3	RESTROOM		
AP-106	10	STUDY ROOM	DARK BLUE SIGN WITH WHITE ROWMARK	
AR-105	-	MANAGERS OFFICE	DARK BLUE SIGN WITH WHITE ROWMARK	
AR-103	-	FOCUS ROOM		
AR-108	-	MEETING ROOM	DARK BLUE SIGN WITH WHITE ROWMARK	
AR-111	-	STORAGE		
AR-111	-	STORAGE		
DIRECTIONAL				
TYPE	QTY	PICTOGRAM	MESSAGE	COMMENTS
MAIN LEVEL				
DB	1 13		SELF CHECKOUT	
DP	1 9, 10, 12, 17, 18		-	FOR MESSAGE, SEE VECTOR FILE PROVIDED
INFORMATIONAL				
TYPE	PICTOGRAM	QTY	MESSAGE	COMMENTS
LOWER LEVEL				
IF-1	6, 7	1	-	
IF-6	-	1	WHEELCHAIR LIFT	
IF-7	-	1	STAFF ONLY	CENTER ON DOOR, 60" AFF
IS	-	25	-	CONFIRM MESSAGE WITH OWNER
MAIN LEVEL				
ID-1	14	1	RETURNS	
IF-2	-	1	HOLDS	
IF-3	15	1	BUSINESS CENTER	
IF-4	16	1	PUBLIC COMPUTERS	
IF-5	4	1	INFORMATION	
IF-6	-	1	WHEELCHAIR LIFT	
IF-7	-	1	STAFF ONLY	CENTER ON DOOR, 60" AFF
IF-8	-	1	PICK UP	DECAL COLOR: WHITE
IF-9	14	1	RETURNS	
IH	11	1	-	FOR TYPE SETTING, SEE AI FILE PROVIDED
IS	-	7	-	CONFIRM MESSAGE WITH OWNER
CUSTOM GRAPHIC				
TYPE	QTY	MESSAGE	COMMENT	
LOWER LEVEL				
GF-1	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
MAIN LEVEL				
GF-2	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-3	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-4	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-5	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	
GF-6	1	-	FILM-1, FOR ARTWORK SEE VECTOR FILE PROVIDED	




MAIN LEVEL SIGNAGE PLAN | A762




1 EXTERIOR ELEVATION - IH
A763 1/4" = 1'-0"




2 EXTERIOR ELEVATION - ID-1 & IF-8
A763 1/4" = 1'-0"




3 100 ENTRY - IF-2 & DB
A763 1/4" = 1'-0"




4 100 ENTRY - IF-4
A763 1/4" = 1'-0"




5 100 ENTRY - IF-3, IF-5, DIR
A763 1/4" = 1'-0"




10 108 MEETING - GF-6
A763 1/4" = 1'-0"




6 111 CHILDRENS - GF-2, GF-3, GF-4, GF-5
A763 1/4" = 1'-0"




11 107 CIRCULATION - GF4, GF-5
A763 1/4" = 1'-0"



7 005 STUDY - GF-1
A763 1/4" = 1'-0"



8 003 STAFF BREAKROOM - IF-1
A763 1/4" = 1'-0"



9 004 ADULT COLLECTION - IS
A763 1/4" = 1'-0"

Drawing 2024 Copyright MSR Design & Architecture, Ltd. 7/20/24 9:11:22 AM
 C:\Projects\2024\11_LAN_A763_Signage_Package\Signage.dwg